Bruhat Bengaluru Mahanagara Palike

EIRL - STATEMENT

BRUHATH BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

FORM OF EXTRA ITEM RATE LIST IN FORM NO. P.W.G.71.

Name of work:- Modified Estimate for Construction of samudaya Bhavana at 5th phasae Yelahanka in Someshwara Ward No-03 Yelahanka New Town Sub Division.

Estimated Cost RS:-25.00 Lakh,s

Agency:-Sri.C.HEMA GNANESH (SRI KRISHNA CONSTRUCTIONS)

Approved Tender Amount RS:- 1908633.00 (EXcluding GST 18%)

Work Order No:-EE/YNK.D/E-PMT-12/W.0/118/2022-23. Dated:14.02.2023

Tender Premium: (-)9.91% Below

Modified Sl.No	EIRL Sl. No.	Description of work	Unit	Qty	Rate	Amount	Whether the items are alternative to the item in the tender, whether these are additional items or sometimes in Accepted tender	Whether the extra items are included in the sanctioned estimate	How the extra cost of the item is proposed to be met	Whether the cost of the item is included in the CSR, if not a Data Rate has to be derived	Remarks
1	2	3	4	5	6	7	8	9	10	11	12
13	E-1	Providing Thermo-Mechanically Treated bars of grade Fe-550 Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position, binding and anchoring to adjacent members whereever necessary complete as per Design including cost of material, labour, usage charges complete as per specifications. (The laps and wastages shall not be measured separately) (Vol- 2 P.No. 84/I.No. 11.32 of PWD SR 2021-22 1st Corrigenda)	kg	3264.85	87.21	284718.47	Yes	No	Under the savings of the Sanctioned Estimate	Yes	As per Work condition
					Total RS	284718.47					

Total Amount of Sanctioned Tender	=	1908633.00
Net Excess Amount of EIRL	=	284718.47
Total % excess to the Tendered Amount	=	14.92 %

Assistant Engineer
Ward No-03

Assistant Executive Engineer
Yelahanka New Town Sub Division

ಸಹಾಯಕ ಕಾರ್ಯ ಪಾಲಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ಉಪನಗರ ಉಪವಿಭಾಗ.
ಜ ಜ.ಎಂ.ಕ. ಬೆಂಗಳೂರು-106

Executive Engineer
Yelahanka Division

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿ